

**MAHARASHTRA FILM, STAGE & CULTURAL DEVELOPMENT CORPORATION LTD.,  
DADASAHEB PHALKE CHITRANAGARI, GOREGAON (EAST), MUMBAI 400 065**

---

**Quotation**

Sealed percentage rate quotations are invited from experienced contractors for ,  
“ **Miscellaneous repair work at play garden & at Jt.m.d.Bungalow.**”

The details of work is as below :-

**Name of the work** : **Miscellaneous repair work at play garden & at  
Jt.m.d.Bungalow.**

**Estimated Cost** : **Rs.8,43,440.69 ( excluding GST )**

Issue of blank quotation form : 15.03.2023 TO 23.03.2023

Last date of receipt of quotation : 23.03.2023

Date of opening of quotation : 23.03.2023

The blank quotations can be obtained from the office of Dy. Engineer (Civil),  
Maharashtra Film, Stage and Cultural Development Corporation Ltd., Dadasaheb Phalke  
Chitranagari, Goregaon (East), Mumbai 400 065 on all working days.



**Deputy Engineer (Civil)**

**Film city, Goregaon**

**Note :-** Quotations to be submitted  
by online only on e-mail ' [decivilmfscdc@gmail.com](mailto:decivilmfscdc@gmail.com)

Name of Work:		Miscellaneous repair work at play garden & at Jt.m.d.Bungalow.			
QUOTATION					
Quantity	Item no.	Description of Item	Rate	Unit	Amount
28.50	1	Excavation for foundation in hard murum including removing the excavated material upto distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete.(Lift upto 1.50 m) By	383.25	m3	10922.63
13.68	2	Dismantling stone masonry in lime or cement mortar including stacking the materials as directed with all leads, lifts	399.00	m3	5458.32
115.20	3	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete...	54.60	m2	6289.92
15.35	4	Providing and laying Cast in situ/Ready Mix cement concrete in M20 of trap/ granite/quartzite/gneiss metal for steps including steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete	7057.05	m3	108325.72
36.48	5	Providing uncoursed rubble masonry of trap / granite / quartzite / gneiss stones in cement mortar 1:6 in superstructure including racking out joints when plastering is to be done / striking joints when no plastering is to be done on inside watering and scaffolding etc. complete..	5810.70	m3	211974.34
85.05	6	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 Kilogram per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days	670.95	m2	57064.30
97.20	7	Providing tuck pointing with cement mortar 1:3 for stone/Brick masonry including scaffolding and curing etc. complete...	187.95	m2	18268.74
64.80	8	Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete	37.80	m2	2449.44
64.80	9	Providing and applying washable oil-bound distemper of approved colour and shade to old and new surfaces in two coats including scaffolding, preparing the surfaces.(excluding the primer coat.) etc. complete...	50.40	m2	3265.92
20.20	10	Providing and laying weep holes of 100 mm diameter PVC pipes as per drawing for abutment returns, return walls etc. Complete	559.65	rmt	11304.93



60.00	11	Providing dry rubble stone pitching 23 cm (about 9 ) thick including all material, quarry spalls, labour etc. complete.	433.65	m2	26019.00
1.94	12	Providing, fabricating and erecting at site of work the tubular steel structure (shed) as per standard design and specifications having various spans in between trusses and in multiples of standard length of bays as specified as per standard specifications, inclusive of cost of steel tubular trusses, tubular columns purlins, tie runners, foundation bolts, base plates, nuts and bolts, welding wherever required etc. as per detailed drawing inclusive of one coat of anticorrosive paint and two coats of oil painting of approved quality and shade etc. complete. Spec. One Number : As	120572.55	MT	233910.75
1.80	13	Providing and fixing M.S. grill door 24 Kilogram/ One Square Metre of various size as per detailed drawings without hot dip coating, iron fixtures and fastenings and 3 coats of oil painting etc..	3420.90	m2	6157.62
12.00	14	Providing and fixing Guard Railing of 1000 mm height in 25mm M.S. square bars 100 mm C/c. as per Type drawing No. 6 dt. 20-8- 85 and fixed in 50mm x 50mm x 6mm iron angle embedded in 1:2:4 C.C. bedding 55 x 45 cm and 50 x 6 iron patti as per detailed drawing with 3 coats of approved yellow and black paint.( item of M.S.Grill is not available in e-SSR 2022-23 hence similar items of Guard railing	3403.05	Rmt	40836.60
10.00	15	Removing other type truss below 5 metres span from roof and stacking the materials as directed with all leads and lifts etc. complets	918.75	no	9187.50
5.00	16	Removing any kind of debris including loading in truck & conveying to approved dumping point beyond MCGM limits, unloading, spreading etc. complete	6778.01	trip	33890.06
26.41	17	Providing and fixing UPVC Roof made up of 3 layers roofing material of thickness 2mm having width of 1130 mm and of required Length having Tensile strength not less than 330 Kilogram/cm2, including fastening with self drilling screw having washers made of stainless steel etc. complete.	1673.70	m2	44202.42
10.00	18	Supply of fabricator / welder for miscellaneous work. ....Labour rates..Welder Skilled.	710.85	day	7108.50
10.00	19	Supply of fabricator / welder for miscellaneous work. ....Labour rates..Semi Skilled Labour.	680.40	day	6804.00
		Total of Work portion		Rs.	843440.69

  
Deputy Engineer(C )  
Filmcity, Goregaon

I herewith quoted.....% above / below / At Par of estimated cost.

Contractors Signature & Stamp